$\label{eq:project} \mbox{PROJECT TITLE: } \mbox{\bf PUBLIC PLAZA TRANSFORMER \ PAD-PHASE 2}$

LOCATION : ZULUETA ST., BRGY. 3, SILAY CITY

TIE WIRE, ALUMINUM ALLOY, SOFT

SCOPE OF WORKS:

1. ELECTRICAL WORKS

BILL OF MATERIALS AND COST ESTIMATES

	DESCRIPTION	QTY.	UNIT	SIZE/ SPECS.	UNIT COST	AMOUNT
Ι	ELECTRICAL WORKS					
	I-1. POLE					
A.	MATERIALS					
	CONCRETE POLE, PRESTRESSED		PCS.	40', 1400kgs(min load break)		
	CLASS 3					
В.	LABOR					
	CONSTRUCTION FOREMAN					
	ELECTRICIAN					
	LABORER					
	I-2. PRIMARY ASSEMBLY					
Α.	MATERIALS					
	CARRIAGE BOLT		PCS.	3/8" x 4-1/4",		
				HOT DIPPED GALVANIZED		
	DOUBLE ARMING BOLT		PCS.	5/8" x 20",		
				HOT DIPPED GALVANIZED		
	DOUBLE ARMING BOLT		PCS.	5/8" x 22",		
				HOT DIPPED GALVANIZED		
	MACHINE BOLT		PCS.	1/2" X 10'		
				HOT DIPPED GALVANIZED		
	MACHINE BOLT		PCS.	1/2" X 6'		
				HOT DIPPED GALVANIZED		
	EYE BOLT, OVAL, FORGED		PCS.	5/8" X 12"		
				HOT DIPPED GALVANIZED		
	BRACE, CROSSARM, STEEL, FLAT		PCS.	28" LONG		
				HOT DIPPED GALVANIZED		
	BRACE, CROSSARM, STEEL, FLAT		PCS.	7" LONG		
	DIAGONAL			HOT DIPPED GALVANIZED		
	BRACKET, INSULATED		PCS.	W/O 3" GROOVE SPOOL		
				INSULATOR		
	CLAMP, CONDUCTOR DEADEND		PCS.	#1/0		
	STRAIN					
	CLAMP, CONDUCTOR		PCS.	#1/0		
	LOOP DEADEND		DGG	MOT DEPEND OF THE STATE		
	CLEVIS SECONDARY SWINGING,		PCS.	HOT DIPPED GALVANIZED		
	WITHOUT SPOOL		DCC	2" 4" 0' HDC		
	CROSSARM, STEEL		PCS.	3" x 4" x 8', HDG		
	INSULATOR, PIN, PORCELAIN,		PCS.	7.2/12.5kV, ANSI 55-4		
	BROWN		PCS.	3" GROOVE Ø, ANSI		
	INSULATOR, SPOOL		PCS.	Class 53-4		
	INSULATOR, SUSPENSION, CLEVIS		PCS.	#6, 10000#		
	CLEVIS TYPE		i Cs.	πο, 10000π		
	NUT, EYE, CONVENTIONAL		PCS.	5/8" Ø		
	LOCK NUT, MF TYPE		PCS.	1/2" Ø		
	LOCK NUT, MF TYPE		PCS.	3/8" Ø		
	LOCK NUT, MF TYPE		PCS.	5/8" Ø		
	PIN, CROSSARM, LONG SHANK		PCS.	1" Ø., 5" LONG		
	ARMOR ROD, ACSR PREFORMED		SETS	#1/0, DOUBLE SUPPORT		
	TAPE, ARMOR, ALUMINUM ALLOY		MTS.	0.05' x 930'		
	WASHER, ROUND		PCS.	1-3/8" Ø, 12GA., 9/16" HOLE		
	WASHER, SQUARE FLAT		PCS.	2-1/4" x 2-1/4" x 3/16",		
				13/16" HOLE		
	TIE WIRE ALLIMINIM ALLOY SOFT		MTS	#4 AWG SOLID		

#4 AWG, SOLID

MTS.

B. LABOR

CONSTRUCTION FOREMAN ELECTRICIAN LABORER

I-3. SECONDARY ASSEMBLY

A. MATERIALS

MACHINE BOLT PCS. 1/2" x 10",

HOT DIPPED GALVANIZED

MACHINE BOLT PCS. 5/8" x 10",

HOT DIPPED GALVANIZED

LOCK NUT, MF TYPE PCS. 1/2" Ø LOCK NUT, MF TYPE PCS. 5/8" Ø

SECNDARY RACK INSULATOR PCS. 3-SPOOL, 8" SPACING W/

SPOOL

WASHER, ROUND PCS. 1 -3/8" Ø, 12GA., 9/16" HOLE

WASHER, SQUARE, FLAT PCS. 2-1/4" x 2-1/4" x 3/16",

13/16" HOLE

TIE WIRE, ALUMINUM ALLOY, SOFT MTS. #4 AWG, SOLID

B. LABOR

CONSTRUCTION FOREMAN ELECTRICIAN LABORER

I-4. GROUNDING ASSEMBLY

A. MATERIALS

CONNECTOR, COMPRESSION PCS. YHD150 CONNECTOR, GROUND ROD (CLAMP) PCS. 5/8" Ø STEEL GROUND ROD, STEEL PCS. 5/8" Ø X 10'

WIRE, GROUND, SOFT IRON MTS. CLASS C, 5/16'Ø, S-STRAND

B. LABOR

CONSTRUCTION FOREMAN ELECTRICIAN LABORER

I-5. GUY ASSEMBLY

A. MATERIALS

ATTACHMENT, BUY, FORMED STRAP PCS. 5/8" BOLT MACHINE BOLT PCS. 5/8" x 10",

CABLE EXTENSION ARM SETS HOT DIPPED GALVANIZED

26-1/2" to 44-1/2" FROM CENTER OF POLE, 3 - 1/2" X 2- 1/4" X 5/16" WITH T -SUPPORT, 2-1/4" X 2-1/4" X

14"

CLAMP, ANCHOR BONDING PCS. SINGLE EYE ROD

CLAMP, GUY STRAIGHT, LIGHT DUTY\ PCS. 3-BOLT, 7/16" MAX.

POLE CLAMP, TYPE RL PCS. HOT DIPPED GALVANIZED CONNECTOR, COMPRESSION PCS. #6-#1/0 to #6-#2, YHD150 GUY GUARD, FULL ROUND YELLOW PCS. 8 ft. PLASTIC, 1" Ø

NUT, LOCK, MF TYPE PCS. 5/8" Ø

WASHER, SQUARE, FLAT PCS. 2-1/4" x 2-1/4" x 3/16",

13/16" HOLE

GROUNDING WIRE, ALUMINUM MTS. #4 AWG, 3-STRAND, MHD

WIRE, GUY, STEEL, HIGH STRENGTH MTS. 7-STRAND

B. LABOR

CONSTRUCTION FOREMAN ELECTRICIAN LABORER

I -6. ANCHOR ASSEMBLY

A. MATERIALS

ANCHOR LOG, TREATED PCS. 8" Ø x 4' - 8,000#

ROD, ANCHOR, THREADED, THIMBLE PCS. 5/8" x 7'

EYE

WASHER, SOUARE, FLAT PCS. 4" x 4" x 1/2", 3/16" HOLE

TOTAL OF MATERIALS

B. LABOR

CONSTRUCTION FOREMAN ELECTRICIAN LABORER

I-7. TRANSFORMER ASSEMBLY

A. MATERIALS

DOUBLE ARMING BOLT PC. 5/8" x 18",

HOT DIPPED GALVANIZED

EYE BOLT, OVAL, FORGED PC. 5/8" x 14",

HOT DIPPED GALVANIZED

THW WIRE, STRANDED (SEC. LEAD) MTS. #2 AWG
THW WIRE, STRANDED (PRIM. LEAD) MTS. #500 MCM
U-BOLT CONNECTOR PCS. #2 COPPER
U-BOLT CONNECTOR PCS. 500 MCM
FUSE LINK, UNIVERSAL, BOTTOM PCS. 25k

HEAD

NUT, GALVANIZED PCS. $5/8" \emptyset$ LOCK NUT, MF TYPE PCS. $5/8" \emptyset$

TRANSFORMER, 2HV BUSHING,
ROTARY TAP CHANGER

UNITS
167 kVA, 7.62/13.2Y120/240V, 60Hz ADDITIVE,
COPPER TO COPPER PRIM

COPPER TO COPPER PRIM & SEC. WINDING

WASHER, SQUARE, FLAT PCS. 2-1/4" x 2-1/4" x 3/16",

13/16" hole

B. LABOR

CONSTRUCTION FOREMAN ELECTRICIAN LABORER

I-8. MISCELLANEOUS ASSEMBLY

A. MATERIALS

LIGHNING ARRESTER PCS. 10 KV

CONNECTION, COMPRESSION PCS. #6-#1/0 to #6-#2, YHD150 CONNECTOR, HOTLINE CLAMP PCS. #336-6 run to #2/0-6 FUSE CUTOUT PCS. 100 Amp. 7.8/13.5kV

FUSE LINK, UNIVERSAL, BOTTOM PCS. 25k, 25A

HEAD

INSULATOR, PIN, PORCELAIN, PCS. 7.2/12.5kV, ANSI 55-4

BROWN

PIN, CROSSARM, LONG SHANK PCS. 1" \emptyset , 5" LONG

CONDUCTOR:

CONDUCTOR, BARE, ACSR MTS. #1/0 AWG, 6/1 STRAND

B. LABOR

CONSTRUCTION FOREMAN ELECTRICIAN LABORER

I-9. OTHERS

A. MATERIALS

CONDUCTOR, XLPE COPPER MTS. #1/0 AWG CONDUCTOR, POLY INSULATED, MTS. #500 MCM

COPPER

CROSSARM, STEEL PCS. 3" x 4" x 8', HDG

B. LABOR

CONSTRUCTION FOREMAN ELECTRICIAN LABORER

I-10. PRIMARY METERING ASSEMBLY

A. MATERIALS

PVC ADAPTER, MALE PCS. 1" \emptyset

AUTO WIRE MTS. #10 AWG, STRANDED,

8 ASST. COLORS

CLOSE NIPPLE PCS. 1" x 2" x 1" Ø CONDUCTOR, THW, COPPER MTS. #1/0 AWG CONDULET "T" PCS. 1" Ø PVC COUPLING 1"Ø PCS. ELECTRICAL TAPE ROLLS BIG PCS. ERICSON COUPLING 1"Ø

GUY GUARD, FULL ROUND YELLOW PCS. 8FT. PLASTIC, 1" Ø kWH METER, TRANSFORMER RATED UNIT 3PH, 4-WIRE, CL20, 120-BOTTOM CONNECTED, DIGITAL WITH 480V, 60 Hz, FORM 48A, TA 5 YEARS WARRANTY BATTERY 2.5, KH 1.8, MODEM READY

2.5, KH 1.8, MODEM READY W/ FF. SOFT SWITCHES: TOUT (T SWITCH), kVAR (K SWITCH), EVENT LOG (E SWITCH), BASIC RECOR DING (R SWITCH), GEKV2C FITZALL, BRAND NEW W/ ERC SEAL & CERT., 3PH SERVICE (CT RATED)

LOCKNUT & BUSHING PAIRS 1"Ø RUBBER TAPE ROLLS BIG PVC SOLVENT CAN 120CC

CURRENT TRANSFORMER UNITS OUTDOOR TYPE, WOUND

TYPE, 15 KV, 110 KV BIL, CTR 20:5A W/ ADAPTER PLATES & TERMINAL CON-NECTOR, ANSI ACCURACY CLASS, 0.3 THRU B-2, PATING FACTOR = 1.5 @ 30°

RATING FACTOR - 1.5 @ 30° C. FREQ. = 60 HZ., DRY TYPE CAST RESIN INSULATION OUTDOOR TYPE, 8400:120V

POTENTIAL TRANSFORMER UNITS OUTDOOR TYPE, 8400:120V

VOLTAGE RATIO 70:1,110 BIL, SINGLE BUSHING W/ ADAPTER PLATES & TERMI-NAL CONNECTOR, ANSI ACCURACY CLASS, 0.3 THRU BURDEN Y, DRY TYPE, CAST RESIN INSULATION

THW WIRE, STRANDED MTS. #6 AWG, GREEN

B. LABOR

CONSTRUCTION FOREMAN ELECTRICIAN LABORER