

Project Title: **REPAIR OF PUBLIC MARKET ROOFING-BLDG-1**
 Location : **SILAY PUBLIC MARKET, SILAY CITY**

SCOPE OF WORKS

1. VENTILATION, GUTTER & TINSMITHRY WORKS

BILL OF MATERIALS AND COST ESTIMATES

| | DESCRIPTION | QTY. | UNIT | SIZE/ SPECS. | UNIT COST | AMOUNT |
|------------|--|------|--------|-------------------------|-----------|--------|
| I | DEMOLITION & CLEARING | | | | | |
| | A. MATERIALS | | | | | |
| | CROW BAR | | PCS. | HEAVY DUTY | | |
| | B. LABOR | | | | | |
| | LABORER | | | | | |
| II | GUTTER REPAIR (260 LN.M.) | | | | | |
| | A. MATERIALS | | | | | |
| | STEEL ANGLE BAR | | LGTHS. | 1" X 1" X 1/4"THK. | | |
| | STEEL FLAT BAR | | LGTHS. | 1" X 1/4"THK. | | |
| | PRE-FAB GUTTER | | PCS. | 0.5MM THK,STAINLESS | | |
| | WELDING ROD | | BOXES | 1/8" Ø (60-13) | | |
| | METAL PRIMER | | GALS. | PREMIUM | | |
| | PAINT THINNER | | GALS. | PREMIUM | | |
| | PAINT BRUSH | | PCS. | 2" | | |
| | TEKSCREW | | BOXES | 2 1/2" | | |
| | BLIND RIVETS | | BOXES | 3/4" X 1/2" | | |
| | CUTTING DISC | | PCS. | 4" DIA. | | |
| | HACKSAW BLADE | | PCS. | | | |
| | PVC PIPE | | PCS. | 4" DIA., ISO CERT. | | |
| | PVC ELBOW | | PCS. | 4" X 4" DIA., ISO CERT. | | |
| | ACRYLIC PAINT | | GALS. | PREMIUM | | |
| | SOLVENT CEMENT | | CANS | 200CC | | |
| | B. LABOR | | | | | |
| | CONSTRUCTION FOREMAN | | | | | |
| | TINSMITH | | | | | |
| | PLUMBER | | | | | |
| | LABORER | | | | | |
| III | VENTILATION INSTALLATION (LUMPSUM) | | | | | |
| | A. MATERIALS | | | | | |
| | PLAIN G.I. SHEET (FOR SIDINGS) | | SHTS. | 0.5MM THK. | | |
| | TEKSCREW | | BOX | 2 1/2" | | |
| | INDUSTRIAL ROOFTOP TURBINE | | SETS | 600MM BALL DIA. | | |
| | AIR VENTILATOR (INCLUDING INSTALLATION) | | | | | |
| | B. LABOR | | | | | |
| | CONSTRUCTION FOREMAN | | | | | |
| | TINSMITH | | | | | |
| | LABORER | | | | | |